
When?

- During road construction
- During road maintenance
- During utilities work

TRAFFIC MANAGEMENT DURING CONSTRUCTION.

Traffic Management Plan (TMP) is a site-specific plan that covers the design, implementation, maintenance and removal of temporary traffic management (TTM) measures while work or activity is carried out in the road corridor (road, footpath or berm).



Traffic Management Plan



- Good arrangement of traffic control




- Good arrangement of traffic devices _
 - Sufficient temporary luminaries _



- Barriers appropriate arrangement - Barriers serve as channelizing devices







- Workers and machineries exposed to hazard

Traffic Control Devices Criteria

Traffic Control Devices	Type/Where to use
Concrete Barrier	 Work area contain heavy machineries / rigid structure / stock pile Work area different level more than 1m
Plastic Barrier (interlock)	 Work area different level less than 1m Plastic barrier must be filled with water/sand
Blinker	- Use on channelizing device
String delineator	 Use as supplement on channelizing devices in outlining the correct vehicle path Reflective unit minimum 75mm dimension
Warning lamps	 Portable type and light emitted shall be yellow (amber) Use on channelizing devices and signs
Floodlights	 Light work activities or hazardous area at night Providing temporary luminaries at certain location
Flagmen	 To stop, proceed or slowing the traffic Flagger should be wearing visible clothing (orange or fluorescent)
Temporary Signage	 High Intensity Prismatic Retro-reflective sheeting on their faces



Prepared by : Road Safety Audit Division Road & Bridge Engineering Specialist, Road Branch. Public Work Department.