



Table of Contents

1.0 TESTING, ADJUSTING, BALANCING AND COMMISSIONING REQUIREMENTS	3
1.1 GENERAL	3
1.2 INSPECTION AND TESTING PLAN (ITP)	4
1.2.1 Final Acceptance Test	6
1.2.1.1 Switchboard Factory Test	6
1.2.2 Delivery Stage	7
1.2.3 Installation Stage	7
1.2.3.1 Visual Inspection	8
1.2.3.2 Refrigerant Leak Test	8
1.2.3.3 Refrigerant Charge Test	9
1.2.3.4 Purging/ Flushing	9
1.2.3.5 Duct Leak Test and Duct Flushing	9
1.2.3.6 LV Motors, Switch Gears and Cabling Insulation Test	9
1.2.3.7 Cable Continuity Test	10
1.2.3.8 Pipe Gradient Test	10
1.2.4 Functional Performance Test	10
1.2.4.1 Pre-Functional Performance Test	10
1.2.4.2 Air Cooled Package Unit (ACPU)	11
1.2.4.3 Switchboard and Power Supply	13
1.2.4.4 Air Distribution	14
1.2.4.5 Infiltration Test	15
1.2.4.6 Wall Insulation and Sprayed PU Foam Insulation Effectiveness Test	15
1.2.4.7 Mechanical Ventilation Test	16
1.3 COMMISSIONING	18
1.3.1 Handing Over Documents	18
1.3.2 System Familiarisation Program	19
2.0 POST OCCUPANCY EVALUATION	20
3.0 TESTING INSTRUMENTS & ACCESSORIES	21



List of Tables

<i>Table 1 : Sample of Inspection and Testing Plan</i>	<i>5</i>
<i>Table 2 : Switchboard Testing</i>	<i>7</i>
<i>Table 3 : Test List In Installation Stage.....</i>	<i>8</i>
<i>Table 4 : ACPU Inspection and Test.....</i>	<i>11</i>
<i>Table 5 : ACPU Control Test Requirements</i>	<i>12</i>
<i>Table 6 : Switchboard and Power Supply Inspection and Test Requirements</i>	<i>13</i>
<i>Table 7 : Air Distribution System Inspection and Test Name.....</i>	<i>14</i>
<i>Table 8 : Mechanical Ventilation System Inspection and Test Name</i>	<i>16</i>
<i>Table 9 : Fan Control Test List.....</i>	<i>17</i>
<i>Table 10 : Post Occupancy Evaluation Form.....</i>	<i>20</i>
<i>Table 11 : Testing Instruments</i>	<i>22</i>



1.0 TESTING, ADJUSTING, BALANCING AND COMMISSIONING REQUIREMENTS

1.1 GENERAL

This section specifies the requirements for all testing, adjusting, balancing and commissioning (TABC) of mechanical works to be carried out under the contract. The objectives of TABC are;

- i. To verify the delivered materials are as per approved specification and good physical condition.
- ii. To verify the installation works are carried out in accordance to specification and good engineering practises.
- iii. To verify the performance in terms of functionality, safety, maintainability and operational ability of the installed equipment/systems meet the specified design intention through series of tests and adjustments.
- iv. To ensure all test results are systematically recorded and verified prior to system commissioning.

TABC works are divided into four stages as the following;

- i. Final Acceptance Test.
- ii. Delivery stage.
- iii. Installation stage.
- iv. Functional Performance Test stage.

Contractor shall submit Inspection and Testing Plan (ITP) of TABC works to be carried out in accordance to this specification for Superintending Officer (S.O) review and approval.



1.2 INSPECTION AND TESTING PLAN (ITP)

ITP shall consist of;

i. List of all TABC Requirement

All TABC works with specific scope and boundaries shall be clearly stated at every stage of TABC works.

ii. TABC Work Schedules

TABC work schedules shall be integrated into main project schedules.

iii. Method Statements

TABC method statements shall consists of TABC procedures, responsibilities, necessary tools, measuring equipment and accuracy, consumables and acceptance criteria. Type of test required is listed in Schedule of Inspection and Testing.

Method statements and acceptance criteria for all equipment installation stage inspection and functional performance testing shall be endorsed by manufacturer or manufacturer's valid representative.

Acceptance criteria shall be stated as per Schedule of Design Requirements, technical specification or any applicable standards.

ITP shall be updated for any changes and resubmitted to the S.O/S.O's representative for approval.

Prior to the commencement of the TABC works as per approved ITP, contractor shall issue Request for Inspection and Testing (RFIT) to the S.O. During the TABC, contractor shall have his supervising foremen and mechanics available to aid the testing and to perform any adjustments as directed. The TABC works shall be carried out under the direction of experienced personnel and witnessed by S.O or S.O's representatives. No subsequent installation works shall proceed without S.O's approval of the test result.

Depending on the specific demands of individual installation, S.O's Representative may require additional or substitute testing works in regard to any elements in the installation other than those indicated in this specification.



Table 1: Sample of Inspection and Testing Plan

Stage	Inspection / Test Name	Scope and Boundaries	Responsibility	Method Statement	Test Form No	Expected Date
Final Acceptance Test	Switchboard/ Control Panel Test	Main Switch Board / Control Panel	Manufacturer	MS-ITP-PDI-02	TF-02	17-Feb
Delivery Stage	Equipment verification and physical Inspection	Air Cooled Package Unit (ACP-01)	Contractor	MS-ITP-PDI-05	TF-05	17-Mar
	Equipment verification and physical Inspection	Air Cooled Package Unit (ACP-02)	Contractor	MS-ITP-PDI-06	TF-06	17-Mar
	Equipment verification and physical Inspection	Air Cooled Package Unit (ACP-03)	Contractor	MS-ITP-PDI-07	TF-07	17-Mar
Installation Stage	Charging Gas	Air Cooled Package Unit	Contractor	MS-ITP-PDI-08	TF-08	17-May
	Visual Inspection	Air Side	Contractor	MS-ITP-PDI-08	TF-08	17-May
	Support and hanger load test	Equipment, piping, ductwork	Contractor	MS-ITP-PDI-10	TF-10	17-Jan
	Duct Leak Test	High Pressure above 450 Pa only	Contractor	MS-ITP-PDI-11	TF-11	17-Jan
	Cable continuity and insulation test	All LV cable	Contractor	MS-ITP-PDI-12	TF-12	17-Jan
	Gradient Pipe Test	Condensate drain pipe	Contractor	MS-ITP-PDI-13	TF-13	17-Jan
Functional Performance Stage	Air Cooled Package start-up test	Air Cooled Package Unit	Manufacturer	MS-ITP-PDI-14	TF-14	18-Feb
	Air Cooled Package Performance Test	Air Cooled Package Unit	Contractor	MS-ITP-PDI-16	TF-16	18-Feb



1.2.1 Final Acceptance Test

Final Acceptance Test shall be conducted if stated in the Schedule of Inspection and Testing Requirements and Schedule of Price of this tender document. The equipment shall be witness-tested at Original Equipment Manufacturer (OEM) premises before being delivered to site by not more than three (3) government's representative to be nominated by the Pengarah Kanan Cawangan Kejuruteraan Mekanikal, Ibu Pejabat JKR Malaysia, Kuala Lumpur.

The Contractor shall include in the tender all costs that will be incurred for the Final Acceptance Test at Original Equipment Manufacturer (OEM) premises including food, travelling (air fare, inland transport, airport taxes, etc.) and hotel accommodation not lower than the current Malaysian Government rate for a period of not more than seven (7) working days not inclusive of travelling days.

A factory test shall be define as any test of equipment required as stated in the contract, conducted at manufacturer's plant or at an independent and accredited test facility approved by the S.O.

Performance test method statement, test standard and acceptance criteria shall be submitted to S.O for approval prior to such testing. The manufacturer shall produces a signed test report to be submitted for S.O's approval. Manufacturer shall be responsible for any reworks and adjustment of the equipment if the test results fail to comply to the approved acceptance criteria.

1.2.1.1 Switchboard Factory Test

Switchboard pre-delivery acceptance test shall be carried out before delivery to site. The main circuits and the auxiliary circuits shall be tested to verify dielectric properties with power-frequency test voltage of 2500Vac for 1 minute and insulation resistance under test voltage of 1000V. Switchboard testing shall include inspection and checking of wiring, electrical continuity, functionality of the protective circuits, connections and effectiveness of mechanical actuating elements and logic circuit interlock. Test Results or Certificate duly certified by Competent Person as in Electricity Regulations 1994 shall be issued for every switchboard supplied and installed.



Type of testing for switchboard as per categorization shall be as per Table 2 below:

Table 2: Switchboard Testing

Category	Current Rating	Registration and type of test report
I	$I \leq 600 \text{ A}$	Suruhanjaya Tenaga (S.T)
II	$600 \text{ A} \leq I \leq 1200 \text{ A}$	Suruhanjaya Tenaga (S.T) & Partial Type Test in accordance with MS IEC 60439-1 (i) Short Circuit Test (ii) Temperature Rise Test
III	$I \geq 1200 \text{ A}$	Suruhanjaya Tenaga & Full Type Test in accordance with MS IEC 60439-1

1.2.2 Delivery Stage

All incoming material and equipment to site shall be inspected to verify that delivered items are comply to contract specification, as per approved materials and good physical conditions. Materials delivered to site shall be free from defects and adequately protected against site conditions.

1.2.3 Installation Stage

List of inspection and testing works during installation as per Table 3;



Table 3: Test List In Installation Stage

Inspection/ Test name	System/Component	Objectives
Visual Inspection	Air Side (Support and Hanger, Equipment, piping, ductwork, etc.)	Verify that all installation as per Technical Specification
Refrigerant Leak Test	Refrigerant pipe & Equipment	Verify refrigerant and integrity of all pipe joints and fittings.
Refrigerant Charge Test	Refrigerant pipe	Verify refrigerant gas, pressure & running amp
Purging/Flushing	Refrigerant pipe and drain pipe	Verify that all pipes are internally clean
Duct Leak Test and Duct Flushing	Ductwork	a) Verify integrity of all duct joints and fittings. b) Verify that all ducts are internally clean.
LV Motors, Switch Gears and Cabling Insulation Test	LV Motors, Switch Gears and Cabling	Verify insulation effectiveness
Cable Continuity Test	Electrical Cabling	Verify cable continuity effectiveness
Pipe Gradient Test	Condensate drain pipe	Verify condensate drain pipe gradient as per technical specifications.

1.2.3.1 Visual Inspection

All installation shall be subjected to technical specifications and drawings.

1.2.3.2 Refrigerant Leak Test

During test, all brazing joints, bends, fitting and valves shall be visual checked for any leaks or deformations for the entire piping system. Expanded conditions of all piping shall be carefully studied and any necessary change in hangers, anchors or guide locations shall be made.

Use nitrogen gas or electronic leak detector for refrigerant gas leakage. All pipes, valves, fitting, etc. shall be tested to the minimum of 1.5 times the working pressure, whichever is greater for period of 2 hours.

Pressure and leak tests of refrigerant piping systems are normally carried out on completion of the system, before pipework is insulated.



1.2.3.3 Refrigerant Charge Test

Refrigerant charge test shall be as per manufacturer recommendation.

1.2.3.4 Purging/ Flushing

To eliminate the probability of such chocking and damage, the internal surfaces of the piping system network need to be flushed clean.

Components that can be potentially damaged/choked by particles or debris from the flushing process shall be isolated from the flushing circuit and cleaned individually.

1.2.3.5 Duct Leak Test and Duct Flushing

All high pressure ductwork more than 750Pa static pressure shall be subjected to duct leak test procedure and acceptance criteria in accordance with HVAC Air Duct Leakage Test Manual (ANSI/SMACNA 016-2012). All duct opening shall be sealed prior to duct leak test. Maximum system leakage shall be limited to 5% of design flow. The test result shall be approved by the S.O.

All duct systems shall be flushed according to the requirement of this specification. All fabrication, jointing works and leak test shall be completed and accepted before the flushing procedure. Duct flushing reports shall be submitted to S.O after completion of flushing procedures.

1.2.3.6 LV Motors, Switch Gears and Cabling Insulation Test

Insulation resistance test shall be performed via a megohmmeter with a voltage output of at least 500-1000 dc volts. Each conductor shall be individually test with all other conductors and shields grounded. Test duration shall be one minute and the resistance value shall be recorded.

Step 1- Conducting Time - Resistance Absorption Test Method

The successive resistance reading shall be taken at specific times and the differences in readings shall be recorded. A good insulation shows a continual increase in resistance over a period of time (in the order of 30 to 60 second).

Step 2 - Dielectric Absorption Ratio

The test shall be continuing with Dielectric Absorption Ratio reading by taking resistance value at every minute until 10 minutes to obtain the Polarization Index.

The Polarization Index is the ratio of two time-resistance readings (such as a 10-minute reading divided by a 1-minute reading).



The minimum acceptance value of Polarization Index shall be 1.4 to 1.6 for 60/30 sec Ratio and 2 to 4 for 10/1 minute ratio.

1.2.3.7 Cable Continuity Test

Cable continuity test shall be performed on each power cable by ohmmeter method. Perform an acceptance test on cables, including terminations and joints, after cable system installation and before the cable system is placed into service. In accordance with ANSI/IEEE 400, by means of direct voltage (dc) and recorded in the relevant testing form.

1.2.3.8 Pipe Gradient Test

All drain pipes carrying condensate shall be tested to verify their ability to discharge condenser to the drain point seamlessly without any obstruction or water stagnation.

1.2.4 **Functional Performance Test**

List of functional performance test are as the following. All Functional Performance Test shall commence after all inspection and testing during installation stage has been completed.

1.2.4.1 Pre-Functional Performance Test

a. Air Balancing

Air flow measurement in ducts shall be measured by either pitot tube traverse average method or vane anemometer (depending on site conditions). Balancing damper final position shall be marked on site. Final terminal air flowrate shall be balanced to within $\pm 10\%$ from design value or as per S.O satisfaction.

Air flow rate to each terminal shall be measured by air flowhood with digital manometer and balanced via balancing damper. Total air balancing report shall be produced and submitted to S.O.

b. Accuracy Test

Before the commencement of the functional performance test, the contractor shall carry out field calibration check for the functional accuracy of measuring, regulating and similar equipment, forming part of installation including gauges, transducers, sensors, switches and meters.

All calibration certificates of all measuring facility shall be submitted to the S.O.



1.2.4.2 Air Cooled Package Unit (ACPU)

Table 4: ACPU Inspection and Test

Inspection/ Test name	Objectives
ACPU General Inspection	Verify that equipment physical conditions are acceptable.
Refrigerant Piping Inspection	Verify insulation/ condensation and refrigeration leakage.
Fan Volumetric Air Flow Test	Verify that air flow is as per design flow.
Cooling Coil Performance and COP Test	Verify that coil capacity and COP standard as per manufacturer.
ACPU Refrigerant High/Low Pressure Protection Test	Verify ACPU protection against refrigerant high/low pressure condition
ACPU Control Test	Verify that control system function as per design control strategies.
Noise Level Test	Verify noise level within permissible limit.

a. ACPU General Inspection

ACPU shall be visually inspected for any deviation from approved shop drawings, approved material and identification of any physical defects that may arise during installation works.

b. Refrigerant Piping Inspection

Refrigerant piping installation shall be inspected for any traces of leakage, insulation and condensation.

c. Fan Volumetric Air Flow Test

Air flow measurement in ducts shall be measured by either pitot tube traverse average method or vane anemometer (depending on site conditions). Fresh air flow rate shall be measured via vane anemometer or pitot static tube (single point). All points for pitot tube insertion shall be prepared and reseal adequately after measurement. Blower motor power shall be recorded during measurement.



d. Cooling Coil Performance and COP Test

Air temperature and humidity before and after cooling coil (Off/On coil) shall be spot measured and recorded at anticipated peak and lowest ambient.

Coil performance data and COP test data shall then be analysed and endorsed by manufacturer. Coil performance shall be compared with manufacturer published performance data. Parameters that are beyond recommended operating range shall be identified and rectified.

e. ACPU Refrigerant High/Low Pressure Protection Test

ACPU ability to cut off in the event of excessively high refrigerant pressure and low refrigerant pressure. The test shall be carry out by manipulating high/low pressure switch setting and observe tripping of compressors.

f. ACPU Control Test

Each ACPU control system shall be tested against their design as detail out in Table 5.

Table 5: ACPU Control Test Requirements

Type of ACPU Control	Description
Temperature Control	Adjust thermostat setting above and below controlled parameter value (e.g. return air or space air temperature) and observe response in compressor on/off
Damper Shut Off	For motorised fresh air damper application, ensure damper is closed when ACPU is shut off.
Fire Mode Test	Test interlocking between smoke detector and ACPU trip (control panel). Aerosol spray shall be used to activate smoke detectors and observe tripping of ACPU.

g. Noise Level Test

Noise level measurement shall be carried out via Sound Level Meter Type 2 / Class 2 General Purpose Grade for field use ± 1.0 dB. All measurement points are at a height of 1.5m from the floor at every enclosed space/zone. Measurement shall be made when ACPU is on and another one when in off condition (background noise level).



1.2.4.3 Switchboard and Power Supply

List of Switchboard and power supply inspection and test name are listed in Table 6. Detail method statement for testing shall be submitted conforming to the test requirements in this specification. Only Competent Person as in Electricity Regulations 1994 shall conduct the switchboard testing.

Table 6: Switchboard and Power Supply Inspection and Test Requirements

Inspection/ Test name	Description
Switchboard General Inspection	<ul style="list-style-type: none"> • Verify physical switchboard components are as per specification. • Check for tripping setting and system trip • Check for wiring, motor insulation and record data. • Check for cable terminal tightness. • Check for equipment and panel grounding connection. • Check for any sign for cable heating. Cable temperature shall be measured and verify against IEEE standards for temperature rise during full load. • Check for voltmeter, and ammeter function and accuracy record running voltage and ampere. • Check for control circuit function as intended. • Check for contractors, relays, ACB, MCCB, MCB, type, size and ratings as per specification.
Power Supply Test	<ul style="list-style-type: none"> • Verify that power supply parameters are within permissible range, safety protections are in place and physical condition of switch board and cabling works are acceptable as per specification and approved shop drawings. • Verify rotation of equipment/phase sequencing according to manufacturer recommendation • Verify phase protection relay installation and function.
Overcurrent and Earth Fault Protection	<ul style="list-style-type: none"> • Circuit breaker and Earth Fault Protection calibration and discrimination shall be conducted and coordinated between electrical contactors. • Circuit breaker and Earth Fault Protection shall be tested against simulated leakage current. • IDMT tripping delay shall be selected/programmed suitable for equipment starting overloading preventing nuisance tripping during starting.



1.2.4.4 Air Distribution

List of air distribution system inspection and test name are listed in Table 7.

Table 7: Air Distribution System Inspection and Test Name

Inspection/ Test name	Objectives
Room Condition Test	Verify temperature, humidity and air velocity is within specification.
Pressurisation Test	Verify operating space differential pressure is within specification.
Duct Condensation Inspection	Verify insulation performance to prevent duct condensation.

a. Room Condition Test

Space temperature and relative humidity shall be recorded either by temperature and humidity data logger or spot measurements using sling psychrometer as per S.O instruction. Time of measurement shall coincide with ACPU test period.

Temperature and humidity data logger shall be used to measure temperature and humidity at these locations;

- Location where occupants are known to spend most of their time.
- Furthest zone and high heat load area.
- Main return duct
- Critical areas such as OT room, ICU/CCU/NICU room, Medical Record, High Dependency Ward (HDW), Isolation Room, Central Sterile Supply Department (CSSD), Laboratory, Medical store, Server room as decided by S.O.

For all other areas, spot measurements using sling psychrometer shall be used during anticipated peak and minimum cooling load period as per S.O instructions. Air velocity in spaces shall be measured using hot wire anemometer.

Building operation and weather conditions during testing such as outdoor air temperature and humidity, internal load factors i.e. population, lighting and equipments data shall be recorded.



Room condition test report shall be submitted consisting of the descriptive statistic of the measured data i.e. mean, max, min, range, frequency bin analysis, their respective location and building operation and weather conditions data during testing.

b. Pressurisation Test

In zone where differential pressure requirements are specified, pressurisation test shall be performed via pressure differential meter and verified by smoke test.

c. Duct Condensation Inspection

Visual inspection shall be carried out to determine any traces of condensation on duct surfaces. Any traces of condensation shall be reported.

1.2.4.5 Infiltration Test

Any path for infiltration of outside air or untreated air to the air conditioned space shall be identified visually and reported.

1.2.4.6 Wall Insulation and Sprayed PU Foam Insulation Effectiveness Test

Visual check on trace of condensation at all wall or slab surfaces shall be carried out and reported.



1.2.4.7 Mechanical Ventilation Test

List of mechanical ventilation system inspection and test name are listed in Table 8.

Table 8: Mechanical Ventilation System Inspection and Test Name

Inspection/ Test name	Objectives
Fan General Inspection	Verify that equipment physical conditions are acceptable.
Fan Volumetric Air Flow Test	Verify that air flow is as per design flow.
Fan Control Test	Verify that control system function as per design control strategies.
Noise Level Test	Verify noise level within permissible limit.

a. Fan General Inspection

Fan shall be visually inspected for any deviation from approved shop drawings, approved material and identification of any physical defects that may arise during installation works.

b. Fan Volumetric Air Flow test

Air flow measurement in ducts shall be measured by either pitot tube traverse average method or vane anemometer (depending on site conditions). All points for pitot tube insertion shall be prepared and reseal adequately after measurement. For ductless fan, vane anemometer shall be used.



c. Fan Control Test

Fan control test shall be carried out as per Table 9.

Table 9: Fan Control Test List

Type of Fan Control	Method
Temperature Control	Adjust thermostat setting above and below controlled parameter value and observe response in fan operation. Temperature reading of the served space shall be recorded via temperature data logger for 24 hrs fan operation.
Schedule operation	Adjust timer schedule and observe response in fan operation.
CO ₂ Control	Adjust CO ₂ sensor set point above and below controlled design value and observe response in fan operation. CO ₂ reading of the served space shall be recorded via CO ₂ meter (one off measurement).

d. Noise Level Test

Noise level measurement shall be carried out via Sound Level Meter Type 2 / Class 2 General Purpose Grade for field use ± 1.0 dB. All measurement points are at a height of 1.5m from the floor at every enclosed space/zone. Measurement shall be made when fan is on and another one when in off condition (background noise level).



1.3 COMMISSIONING

Commissioning includes achieving, verifying, and documenting that the performance of facilities, systems, and assemblies meets defined objectives and criteria.

All completed test forms and test summary shall be submitted to S.O's representative for final review and approval. Having satisfied that all appropriate tests have been conducted and the performance of the installation meet the design objectives; S.O's representative will issue or recommends to the S.O for the issuance of Certificate of Practical Completion (CPC).

1.3.1 Handing Over Documents

After issuance of Certificate of Practical Completion, contractor shall submit all related project handing over documents as the following;

- a) Test Report complete with fully verified Inspection checklist and Test Forms.
- b) Air Balancing Report
- c) Defects List
- d) Operation and Maintenance Manual which includes
 - *Standard/ Manual Operating Procedures*
 - *Preventive Maintenance Schedule and Manual*
 - *Equipment/Product Engineering Data.*
 - *Operation set point (temperature, relative humidity, pressure etc.)*
 - *Switchboard overload setting and set points*
 - *Control valve setting*
 - *Contractor and manufacturer contact details*
 - *Circuit Diagrams*
 - *Inventory List*
- e) As-Built drawings
- f) Schedule of System Familiarization Program to end users.



1.3.2 System Familiarisation Program

In-class and practical System Familiarization Program shall be conducted to the personnel nominated by S.O within one (1) month of issuance of Certificate of Practical Completion. Program shall focus on:

- Overview of design concept and objectives
- Operation instruction & competency requirement
- Maintenance procedures
- Critical operating parameters monitoring and
- Emergency response & safety procedures.
- Environmental protection procedures.

Contractor shall submit program modules and materials to S.O for approval prior to commencement of training. Particulars of trainee shall be recorded and send to S.O for records.



2.0 POST OCCUPANCY EVALUATION

Post Occupancy Evaluation shall be performed by the contractor one (1) month before the end of defect liability period.

Space temperature and relative humidity shall be measured at all respective temperature zone. Temperature, relative humidity and air speed shall be within specification. Any adjustment to the system are required if the data deviate from the specification.

A survey shall be carried out to evaluate user experiences with the air conditioning and ventilation system from comfort, operation ability or any other related problems. Survey form as in Table 10 shall be used. All survey form shall be submitted to S.O for references.

Table 10: Post Occupancy Evaluation Form

Block			
Floor			
Space			
ACPU no			
Room Conditions			
<i>Parameters</i>	<i>Measured value</i>		<i>Comment</i>
<i>Dry Bulb Temperature</i>		°C	
<i>Relative Humidity</i>		%	
<u>User Survey</u>			
1) Any difficulty in operating the system? If Yes, please state the details.			
2) Any specific problem system? If Yes, please state the details.			



3.0 TESTING INSTRUMENTS & ACCESSORIES

All permanent sensors and gauges use for measurement of temperature, pressure and flow shall be factory calibrated and all calibration certificates shall be submitted to S.O prior to testing works.

The contractor shall provide all necessary testing, calibrating instruments and labour required for the testing, adjusting, balancing and commissioning of the air-conditioning and mechanical ventilation system installed under the contract.

The contractor shall also allow for any necessary replacement of parts in order to achieve the conditions specified in the drawings and specification. Provisional sum for that purpose is provided in Schedule of Price.

Testing instruments specification shall be but not limited to as per Table 11.



Table 11: Testing Instruments

Measurement	Type of Instruments	Accuracy
Dry bulb and humidity (logging)	Temperature and Relative Humidity data logger	<i>Temperature measurement accuracy: $\pm 0.5^{\circ}\text{C}$ ($0^{\circ}\text{C} < T < 30^{\circ}\text{C}$) and 1.5% of reading at $30^{\circ}\text{C} < T < 70^{\circ}\text{C}$). Humidity measurement accuracy: $\pm 2\% \text{RH}$ (from 15°C to 25°C)</i>
Dry bulb and humidity (One off)	Sling Psychrometer	$\pm 0.5^{\circ}\text{C}$
Duct air velocity	Pitot Tube and digital manometer	$\pm 0.7 \text{ m/s}$ (from 2 to 5 m/s)
Free air velocity	Vane anemometer	$\pm 3\%$ of reading $\pm 0.1 \text{ m/s}$ (from 0.3 to 3 m/s)
Room air velocity	Hot wire anemometer	$\pm 3\%$ of reading $\pm 0.05 \text{ m/s}$ (from 0.15 to 3 m/s)
Duct thickness	Vernier caliper	$\pm 0.01 \text{ mm}$
Ampere	Clampmeter (instantaneous)	$2.0\% \pm 5 \text{ digits}$ (45-65Hz)
Voltage	Clampmeter (instantaneous)	$1.5\% \pm 5 \text{ digits}$
Combined power, ampere, voltage, power factor and Energy	Power/Energy logger (continuous)	Active Power: $\pm(1.2\%$ of reading + 0.005% of range) (For $\text{PF} \geq 0.99$); $\pm(1.2\%$ of reading + $7 \times (1-\text{PF}) + 0.005\%$ of range) (from 0.6 PF to 0.98PF)
Air volumetric flowrate	Air flowhood with digital manometer	Supply and Exhaust : $\pm 3\%$ of reading
Noise (Full spectrum)	Sound Level Meter Class 1	Class 1 as per IEC 61672-1:2002
Noise (Average)	Sound Level Meter Class 2	Class 1 as per IEC 61672-1:2002
Vibration	Vibration Analyser	$\pm 5\%$ of reading (from 0.01 g to 50 g); where "g" in meter per second square.
Surface temperature	Infrared thermometer	Display accuracy $\pm 1.0^{\circ}\text{C}$
Air differential pressure	Differential Gauge	$\pm 2\%$ ascending