

## QUOTATION

Ref No: PSB\P\Q\AT\20\13010

Date : 13<sup>th</sup> May 2020

**JURUUKUR BAHAN PENGUASA KANAN,  
BAHAGIAN KHIDMAT KOS DAN INOVASI,  
CAWANGAN KONTRAK DAN UKUR BAHAN,  
IBU PEJABAT JKR KUALA LUMPUR**

Tingkat 19, Menara Tun Ismail Mohamed Ali,  
No. 25, Jalan Raja Laut,  
50582 Kuala Lumpur

T : +603-26141417/1423

Attn. : PUAN SR. RAJA NORMAWATI BINTI RAJA AYOB/PUAN WAN NABILAH (wnabilah@jkr.gov.my)  
(pwcic.jkr@1govuc.gov.my)

Dear Mdm,

**RE : MEMOHON MAKLUMAT DAN HARGA TERKINI PRODUK-PRODUK BAHAN BINAAN DARI  
PEMBEKAL BAHAN BINAAN UNTUK JABATAN KERJA RAYA MALAYSIA~(TIMBER FLOOR)**

This is referring to your email dated 5<sup>th</sup> May 2020 regarding the abovementioned matter and we are pleased to furnish our quotation as below for your kind attention and consideration.

Item	Description	Qty	Unit Rate (RM)	Amount (RM)
1.0	<b>DEWAN SERBAGUNA</b> To supply and install of "PERSWOOD" PNEUMATIC TIMBER FLOORING SYSTEM comprising of solid timber strip or block as stated below laid in random length design with 2 layers of 12mm thick WBP plywood, 4.3mm thick genuine natural rubber pads and a layer of vapour proof membrane and c/w sanding and finishing with 1 coat of <b>Strata Base</b> and 2 coats of <b>Strata Pro</b> , a water based polyurethane timber floor varnish to floor.	m <sup>2</sup>		
1.1	Using <b>Kempas</b> block parquet of size 9mm x 50mm x 250/300mm laid in random length design	m <sup>2</sup>	295.00	Rate Only
1.2	Using <b>Kempas</b> tongue and groove strip of size 18mm x 90mm x 300mm-1800mm in random length design	m <sup>2</sup>	250.00	Rate Only
<b>TOTAL C/F</b>				-

Item	Description	Qty	Unit Rate (RM)	Amount (RM)
<b>TOTAL B/F</b>				-
3.0	To supply and install 18mm x 70mm <b>Meranti</b> skirting c/w 2 coats of stain finish to match timber floor.	mr	42.00	Rate Only
4.0	Games line painting using 2 coats of double component polyurethane coating system for badminton court.	court	1,600.00	Rate Only
5.0	Preliminaries	-	L/S	TBA
<b>TOTAL AMOUNT</b>				-

**Validity** : One (1) month from the date hereafter

**Installation Period** : To be advised (TBA)

**Delivery Period** : TBA

**Notes** :

1. Timber is a natural product and subject to varying colour and grain. Therefore, selection of timber for uniformity in colour and grain is not provided for.
2. Electricity, lighting and power point AC 240V 30AMP, max 50m from the installation area, water, hoisting facilities and storage for materials shall be provided to us free of charges during the entire installation period.
3. Quantity is provisional and subject to final site measurement.
4. Provision for making openings, doorway thresholds, inlay dividing strip, non slip nosing tiles, staircase beading and etc are not included at the above rate.

We trust the above would suffice your requirement and please feel free to contact the undersigned should you need further information.

Thank you.

Yours faithfully,  
**PERSFLOR SDN BHD**



**KC WAN**

Marketing Executive

Manager