



PRESENTED BY: Ir. MOHD AZHARI BIN MOHD SALLEH KPPK, BHG STRUKTUR (UNIT KESELAMATAN) CAWANGAN KEJURUTERAAN AWAM DAN STRUKTUR BLOK G, IBU PEJABAT JKR MALAYSIA, KUALA LUMPUR Email: azharims@jkr.gov.my




رَبِّ زِدْنِيْ عِلْمًا وَارْزُقْنِيْ فَهْمًا \* رَبِّ اشْرَحْ لِي صَدْرِيْ وَيَسِّرْلِي أَمْرِيْ \*

Wahai Tuhanku, tambahkan ilmuku dan luaskan kefahamanku. Wahai Tuhanku, lapangkan dadaku dan mudahkanlah urusanku.

# **Presentation area**

- Introduction
- Common construction systems in Malaysia
- -Precast Concrete (PC) components, HKL car park
- --PC frame, floor/wall panels and acotec
- ---hybrid
- ----system formwork
- Quality assurance stages
- Automation dan mekanisasi
- Kilang IBS automasi dan konvensional
- -singapore experience
- --kilang terbesar dunia
- ---30 storey hotel in 15 days?
- ----Modular building
- Seismic resistance buildings

### introduction IBS RECIPE : WORKING IN TANDEM, COORDINATED SYSTEMS




# **General principles of IBS**

- Industrial production of components; prefabrication; precast (under controlled environment, can be in factory/site)
- 2. Labour reduction
- 3. Open building system standard components; Moduler Coordination: MS1064


#### DESIGN CONCEPTS FOR PRECAST CONCRETE BUILDINGS

The design concept of the precast buildings is based on the buildability, economy and standardization of precast components.



### **PERBANDINGAN PENGGUNAAN BURUH**

#### PURATA KESELURUHAN BILANGAN PEKERJA UNTUK PROJEK IBS DAN BUKAN IBS



### Half slab and hollowcore



Half Slab disusun sedia untuk dipasarkan.



Kerja pemasangan Half Slab ditapak bina.



Hollow Core Slab yang siap dipasang.



Hollow Core Slab disusun mengikut saiz.

#### Advantage hollowcore-longer span lesser components



Kerja pemasangan Hollow Core Slab ditapak bina.


#### **2000 BAYS CARPARK - HKL**



## HKL VIDEO

### Hybrid system eg: PC components + CIS concrete









This system were used since 1984. It was the most economical and efficient system for the construction of high rise buildings.

The companies that being implementing the similar to this type of formworks are:-

1.PASCAL FORMWORK 2.SGB 3.EFCO FORMWORK

German

SN. Engie in . Ostucio I hall ci m WFOING DRMWORK SYSTEM – SRI PERANTAU

- Brittain
- Australia



# mon systems





#### PLASFORM FORMWORK SYSTEM – 64 UNITS SECTION 7




#### PKNS Engineering & Construction Bhd (PECB) TUNNEL FORM SYSTEM – 260 unit Kondo Kristal, Section 7, Shah Alam





#### FORMWORK SYSTEM (Slab)








### 50 storey NAZA TOWER doka system (timber panels)







CADANGAN PEMBANGUNAN 2 BLOK MENARA IBU PEJABAT 50 DAN 38 TINGKAT MENGANDUNGI 1 TINGKAT KEMUDAHAN DI ARAS 10, 8 TINGKAT PODIUM TEMPAT LETAK KERETA DI ARAS 2 HINGGA 9 BERSERTA 3 TINGKAT TEMPAT LETAK KERETA DI ARAS BESMEN, DI ATAS LOT 267, 270, SEBAHAGIAN LOT 268, SEBAHAGIAN LOT 324, SEKSYEN 63, JALAN STONOR, BANDAR KUALA LUMPUR UNTUK TETUAN NAZA TTDI SDN. BHD.

### **Floor layout-plastform**




### **Formwork support**






#### **Formwork-individual panels**



### **General data-fasterners**



# QUALITY ASSURANCE STAGES

- **DESIGN** (JKR AND OTHERS INCL. INDEPENDENT CHECKER)
- PRODUCTION/CASTING/STORAGE/ TRANSPORTATION (SYSTEM PROVIDERS/CONTRACTORS)
- CONSTN. STAGE PREFABRICATING /INSTALLATION (CONTRACTORS)
- SUPERVISION audit/component inspections/General requirements (JKR AND OTHERS)





# QA / QC DI KILANG

NO.	ПЕМ	CHECKLIST			
		YES	NO	N/A	REMARKS
6	Age of precast component lifting	1			<ul> <li>* Lifting the precast component from mould to storage yard at 15 Mpa (10 hrs)</li> <li>* Transport the precast component to the construction site after 7 days</li> </ul>
7	Concrete testing	1			* Cube test day 1-28, slump test, others
8	Storage of finish product	1			* Stacking and protected
9	Precast concrete component production process	1			* Mould preparation, bar installation, concreting with vibrating, cutting, lifting, curing and transportation is carried out properly
10	Precast concrete component dimensional accuracy	1			* ± 10 mm
	INSPECTED BY :				INSPECTED BV :












#### **BIM and Mechanization – CIDB CONCEPT**


#### NEED FOR MECHANIZATION IN CONSTRUCTION INDUSTRY

- 1. The work can be done speedily.
- 2. The work can be done in time.
- 3. Large quantity of materials can be handled, so the size of the project can be increased
- 4. The complex projects involving high grade material.
- 5. High quality standards can be maintained.
- 6. Time schedule can be kept.
- 7. Optimum use of material, man power and finance.
- 8. Due to shortage of skilled and efficient man power.






#### THE VALUE CREATION IN INDUSTRIALISED CONSTRUCTION



The value creation of industrialisation can only be established using robotised and automated manufacturing process which is different from current conventional practices (CIB, 2010).


#### **APPLICATION OF MECHANISATION IN CONSTRUCTION**



# **PENGGUNAAN<sup>B</sup>IM**

#### Tekla Structures - C:\TeklaStructuresModels\Tekla Model\Immigresen Bdr Baru Uda\Kuarter for Immigresen - [View 1 - 3d] Image: File Edit View Modeling Analysis Detailing Drawings & Reports Tools Window Help

▯ᄚᄚᇛᅝᅇᅊᆙᄚᄚᇏ▯ᆮᇋᇉᅕᇪᆙᆘᇣᇛᅚᇍᅋᆘᄵᆘᄬᄬᆙᅆᆘᄪᆮᄷᄯᆄᆝᄽᆘᄤᇴᇏᅆᆙᇓᅆᇓᄬᆘᇔᆋᆘᆂᆕᇐᆮᆝᅆᄲᇮᆙᇞᇴᄽᆋᆘᆘᄮᅆᄮᄮᆝᅕᄵᄵᄿᄿᅆᆝᄽᅇ




Screenshot taken (file: 'C:\TeklaStructuresModels\Tekla Model\Immigresen Bdr Baru Uda\Kuarter for Immigresen\SnapShots\snap\_001.png').

- 0 X

- 8 x

#### 😰 Tekla Structures - C:\TeklaStructuresModels\Tekla Model\Immigresen Bdr Baru Uda\Kuarter for Immigresen - [View 1 - 3d]

II File Edit View Modeling Analysis Detailing Drawings & Reports Tools Window Help



**PRECAST COLUMN & STAIRCASE** 

🔏 🖍 🥕 🔳 🎇 Auto 👻 View plane 👻 Outline planes 👻

S 0 Pan Current phase: 1

1 + 0 object(s) selected

- 0 ×


### **BUILDING VIEW (3-D)**

- 0 X

\_ 8 X

III File Edit View Modeling Analysis Detailing Drawings & Reports Tools Window Help

▯ᄚᇛᆝᅇᅊᆝᄚᄚᄚᄭᅟᇊᅋᅊᇔᇊᆝᇍᇛᅚᆂᅖᆁᅋᆘᄵᆝᅊᅊᆘᅆᆝᆊᆮᄼᄮᄫᆝᄽᆘᄟᇃᅘᇏᄜᇞᅆᆡᇞᇓᄚᄤᆝᇓᆋᆋᆘᆿᆕᆕᇐᇊᇦᆄᇮᆝᇞᇴᆑᇴᅖᆝᆘᆘᇧᇓᇾᆝᆘᆿᆕᆕᄽᆃᆘᆃᄮᆝᅕᄵᄵᄿᆞᆇᆝᄽᅇ



# Singapore approach..

Transformation of public housing (publication 2014)



#### The Transformation of Public Housing

- HDB = Affordable Public Housing
- Build 1,000,000 HDB Flats
- > 80% of Singaporeans Live in HDB Flats
  95% Home Ownership

#### How to Achieve Our Objectives...?


The approaches:

- Facilitate cooperation between stakeholders (designers, suppliers and contractors)
- Develop standardisation
- Optimise usage of standard components
- Simplify site operations
- Emphasis on buildable design

#### Transformation of public housing

#### Improvement initiatives


#### Structural Elements – Modular Dimensio



### MODULAR DIMENSIONING

#### **Transformation of Site Machinery**

- Provide financial incentives for contractors to procure machinery
- Improved cash flow of contractors
- Improved productivity
- Implemented Construction Quality Control Management System



### INCREASE SITE MACHINES

# Develop solution and improve production facility

**R&D In Product** 

#### Higher and Denser Developme




#### use battery mould

### **Mechanised Production Processe**

Production of Flat Panels & Solid Walls

Optimisation of factory production space







Vertical Production Using Battery Mo

Productivity Improvement Thru' Wor Process Transformation....

- Encourage more adoption of market available machinery and hand tools
- Develop/customise machinery to re-engineer work processes

#### **Develop a Customised Mechanized Materials Handling System**

Further improvement to prototype:

- Stability and manoeuvrability
- Diesel powered noise and smoke
  - Customised battery/fuel cells of suitable size & capacity
- Increase load carrying capacity



#### Improve Productivity of Precast Production

- Mould cleaning and oiling
- Mould assembly & fixing of reinforcement
- Concreting and Compaction
- Leveling & Trowelling

Promote Higher Level of Mechanisation & Automate The Precast Production System

#### Automated Precast Production System

- Very efficient for production of standardised products
- Flat and with minimum protrusion and profile
- Minimum dowels or projection bars

Complementing the precast automation process:

 A need to customise the production system to suit local practice









•Widths of PC Planks are highly standardised (1.0m & 2.4m)

• Planks lengths required are formed by dividers.

#### - Large Panel Slab (LPS)



NEW PRODUCT

Casting & de-moulding of LPS slab

High quality off form finish requires minimal touch up on site

# 'Conventional' practice

#### **Construction Technology**

#### Conventional Method:

- Manually tracking and coordination of delivery and installation
- Precasters deliver components basing on contractor's demand schedule
- Tower crane & mobile cranes for handling
- Construction activities subjected to weather condition




### **Improvement in construction technology**

**Advanced Construction Technology:** 

- Construction mechanisation & automation
  - Tools & equipment
  - Automation of concrete batching plants
- Automated building system (ABS)
- Computerised & Integrated Construction Management System

# Explore Ways to Improve PC Installation & Hoisting Operations

- Computerised crane system that integrated with assembly and precast plants.
- High capacity pc components lifting hoist



### **PRECAST PLANT-WORLD LARGEST**

- THE LARGEST PRECAST PLANT OF THE WORLD Morton Group built a greenfield site to build the world largest precast plant with an annual precast output that enables the construction of buildings with a total floor space of 525.000 m2.
- SOUTH AFRICA

#### CASTING OF PLANKS – INSTALLING STEEL FRAMING

















### SCANNING OF MOULD








# **STEEL BARS/BRC**



#### **BAR FIXING FRAME**






#### **ROBOTIC BARS SPACERS TO DWG DETAILS**




#### - AND ARRANGING BARS IN TWO LAYERS FOR PLANK





#### mould ready for casting



### auto concrete dispenser




# auto concrete dispenser



# auto concrete dispenser






## **Skimming/finishing**




















# **FINISH PRODUCT**



### **30 STOREY HOTEL IN 15 DAYS**









### FOUNDATION









### FLOORING ELEMENTS









## FIXING OF SERVICES









## LIGHTING TESTINGS









### TRANSPORTION AND INSTALLATIONS









## **CONSTRUCTION IN PROGRESS**










### FIXING OF STAIRCASE AND CLADDINGS










### FURNITURES AND SHADES










### 24 HOURS WORKFRAME









## EARTHQUAKE RESISTANCE







## • ENERGY EFFICIENT BUILDING

## ECO FRIENDLY COMPONENTS















**T**30 17000m<sup>2</sup> hotel





www.broad.com

2:30 / 2:31


☆ □ : :

Dec 12:31

¢ □ []

## MODULAR BUILDINGS






The Green Precast System provides developers a highly flexible building system that delivers strength, cost and time savings, durability, thermal and acoustic efficiencies and provides structurally superior resistance to natural disasters.





### **Floating pontoon**




# **General principles of IBS**

- Industrial production of components; prefabrication; pre-cast (under controlled environment, can be in factory/site)
- 2. Labour reduction
- 3. Open building system standard components; Moduler Coordination: MS1064

### **PERBANDINGAN PENGGUNAAN BURUH**

#### PURATA KESELURUHAN BILANGAN PEKERJA UNTUK PROJEK IBS DAN BUKAN IBS



### KILANG-KILANG KONVENSIONAL IBS

































### Steel Plate Shear Wall (SPSW)

- Lateral force resisting system USA Federal Courthouse, Seattle
- Thin steel plates are installed into a building's structural frames
- Effectively increase the structure stiffness and strength





### **ECONOMY IN DESIGN**

#### (五) 建築物的外觀形狀與耐震性

建築物的造形與耐農能力關係密切。一般而言, 适形簡單規則的 建築設計,能以較低的建材成本, 興建耐農性較佳的建築物:外形花 俏多變的建築設計, 需要較高的建材成本, 以彈補外形上不耐農的耕 陷。擁有外形義特多變的建築國然實心悦目, 但若是購買或建造樓處 作為居住使用時, 應審慎考量耐震安全、經濟性與建築造形三者之間 的平衡。







要形驗單模制的課題設計

外形花們多變的建築設計

#### ■重心愈高,穩定性愈差

「重心」是指物體的質量分佈中心,例如:重球的重心位於球心, 正方體的重心位於兩個科對角的交叉點,而三角形的重心則是位的關 候「中級」的交會點上。







物體的重心如果讀高,輕輕一推使容易倒下。




外形上寬下窄的物體,重心位置高,地震時,容易翻覆。所以, 重心低的建築物相對上較泡碴回。










口形建築採業種設計。即種間以透過相違


#### 退縮建築容易局部受損

「退縮建築」是指建築的菜園或菜些樓層,樓地板面積突兀地大 改變,建築物的立面形狀突然認識。地震時,樓層很縮減受力行為最 為複雜,容易破壞。




#### ■ 梁線不連貫造成耐震力不佳

一棟建築, 檣地板高程不一致,梁線不連貫,當地震發生時,承 受至右兩條橫梁與棲板夾擊的柱子, 容易破壞。



#### ■鄭陳聞距不足

這葉物彼此體關距離不足,地震時可能相互碰撞而震損,尤其, 高度不同的建築,有不同的自然振動過期,更應預留足夠的變形空間, 防範地震過程彼此發生碰撞。



## Seismic Design for Bridges and Buildings

<u>1980s</u>

### PENANG BRIDGE

### **KOMTAR BUILDING, PENANG**

### **SABAH FOUNDATION BUILDING, SABAH**




**KLCC TWIN TOWERS** 



RENANG BRIDGE





### P E N A N G

B

U

Ι

L

D

Ι

N G



F 0 U B N U D A I Т L D Ι Ι 0 N G N

**S** A B A H

> S A B A H

### Slaid UTM



### **Seismic Retrofit Strategies**

#### **Base Isolation:**





Isolated structures

innovative • entrepreneurial • global



## Twin Towers





OWNER: China Central Properties Ltd. (Current owner is RREEF)

ARCHITECT: Minoru Yamasaki & Associates

PROJECT LOCATION: Dalian, China

PROJECT SCOPE: Structural Engineering, Precast Cladding Engineering and Construction Engineering

\PROJECT DETAILS: 43-stories, 89,000 square meter, precast prestressed concrete, grade-A office tower located near the city centre of Dalian, Liaoning Province.

CHALLENGE: This building is located in a high seismic zone on the northeast coast of China

SOLUTION: Structural design for this building involved precast concrete beams, slab soffits and a

precastconcrete façade and parapet cladding system.

RESULTS: This project was completed in record time as the precast design allowed erection of the building structure at a rate of one floor every three days. Completed in 1999.



Fig. 2. Artist's rendering of The Paramount. Photo courtesy: Kwan Henmi, Architecture and Planning, Artist: W. Yeliseyev.

At 39 stories and 420 ft (128 m) high, The Paramount (located in San Francisco, California) is the tallest concrete structure in addition to being the tallest precast, prestressed concrete framed building in Seismic Zone 4 (a double record). It is the first major high rise building to be braced by an architecturally finished exposed precast concrete ductile frame. The reinforcement used to create this seismic ductile frame includes post-tensioning and high strength reinforcing steel. All this represents a major milestone in the development of precast/prestressed concrete. The building is basically an apartment complex, although the lower floors accommodate retail space, vehicle parking and recreational amenities. This article presents the design considerations, construction highlights, research and development, and code approval process that led to the realization of this structure.

## SEKIAN TERIMA KASIH

# 

