

G-FRP VENTURE MARKETING SDN. BHD. (982292-T)

No. 20, Jln Kundang Jaya 1, Perindustrian Kundang Jaya, 48020 Kundang, Selangor D. E.
Tel: 603-6034 1525 / 016-216 5063 / 016-213 4314 Fax: 603-6034 2615 / 2535 Email: sales@g-frp.com.my

Jabatan Kerja Raya Malaysia
Tingkat 19, Menara Tun Ismail Mohamed Ali,
50350 Kuala Lumpur

Our Ref: MQ2018-030/17072

Date: 18-Dec-18

Revised Quotation: -

Tel: 03-26141430

Fax: 03-26910781

Attn: Ms. Siti Safinah

PRODUCT SPECIFICATION : MS1390 : 2010

Re : Quotation For Supply , Delivery & Installation Of "G-FRP" FRP Panel Water Tank
Project : KL

Thank you for your enquiry pertaining to the above matter.

Listed below is our detail quotation for your immediate kind consideration and perusal as follow:-

No.	Tank Dimension			Partition	Volume		MS Painted Skid	Unit Price (RM)	Qty (Nos)	Total Amount (RM)
	L (m)	W (m)	H (m)		(m3)	Gallon				
1	2	2	1	0	4	880.00	'Include'	4,720.00	1	4,720.00
2	1	1	1	0	1	220.00	'Include'	1,770.00	1	1,770.00
3	2	1	1	0	2	440.00	'Include'	2,950.00	1	2,950.00
4	3	1	1	0	3	660.00	'Include'	4,130.00	1	4,130.00
** Delivery Are Base On Full Load Delivery, No Partial Delivery. **										
Remark : There Will Be A Transport Charges Incurred For The Partial & Additional Delivery.										
Remark : 1 m3 = 220 Gals.										TOTAL (RM) : 13,570.00

Note : ** Concrete Plinth To Be Done By Contractor Minimum 500mm To Maximum 1000mm (Height) **

** FRP Panel Tank for 4.0m(H) is not approved by authority and we will not held responsible in any rejection by the authority.

** FRP Panel Tank for 3m height, will be using " 1m x 1.5m panel x 2pcs " as side panel.**

** Opening Holes By Us For Below 2 1/4 Is Using Jam Nut, Above 3" Is Using PN16 Type **

SCOPE OF SUPPLY:-

Tank panel & steel skid base with under coat primer access
Accessories listed below will be PROVIDED ONLY FOR
WATER TANK ABOVE 1.50M(H) :-

- ** Level Indicator -1 Pcs/Compartment
- ** External HDG Ladder -1 Pcs/Compartment
- ** Internal Stainless Steel Ladder -1 Pcs/Compartment

EXCLUDED FROM SCOPE OF WORK:-

- : Pipe Work, Valve, Ball Float Valve, Flange & Nozzle
- : Unloading and Hoisting of goods at site.
- : Crane Rental and Hoisting Equipment.
- : Security of goods at site.
- : Buyer to supply Sufficient water for leakage test.

Installation work can not be done due to the site problem e.g :-

- 1) Concrete Plinth or I-Beam casted at site NOT as per confirmed shop drawing.
- 2) Concrete Plinth or I-Beam Plastering and leveling NOT done and check.
- 3) Water Tank area full of rubbish, debris and or defecation.
- 4) Water proofing NOT done for the water tank areas.
- 5) Restricted site accessible for transport to go in .
- 6) NO tower crane, crane or hoisting equipment provided for unloading and hoisting of goods to be unloaded within 600mm away from the water tank area on the date of delivery.
- 7) Limited spaces designated for installation are covered up with roof or wall.
- 8) Project site NOT ready for delivery or installation of the water tank.
- 9) RM 300.00 - RM 500.00 will charged for Outstation Project if installation works can not be done in every single trip.
- 10) RM 100.00 - RM 200.00 will charged for Klang Valley Project if installation work can not be done in every single trip.

Terms & Conditions :-

Lead Time	@	1 month upon confirmation of order & shop drawing of the tank opening
Validity Period	@	Seven (07) Days.
Delivery	@	To Site
Terms of Payment	@	To Be Discussed

Note : Any cancellation of order upon fabrication of tank, we will imposed a 30% cancellation charges
Please do not hesitate to contact us, if you need more information.

Thanking you in advance and looking forward to our long term business partnership.

Yours faithfully,

GARY TEH 016-216 2518

OPTIONAL : FRP FLANGES

50mm - \$ 60.00 /Nos	200mm - \$300.00 /Nos
75mm - \$ 80.00 /Nos	250mm - \$400.00 /Nos
100mm - \$105.00 /Nos	300mm - \$500.00 /Nos
150mm - \$207.00 /Nos	

